BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

APPROVED TENDER SCHEDULE –'B'

Item No: 46

Name of Work:- Improvements to roads and drains in Amba Bhavani layout in Attur ward no 03Yelahanka New Town Sub Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri SAMBASHIVA REDDY C	
				Rate	Rate in Words
1	KSRRB 300-1. Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. No. 138 S Item No 19.2 SR2015-16	Cum	237.00	100.00	Rupees one hundred only
2	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2015-16	Cum	33.00	255.80	Rupees two hundred fifty five and paise eighty only
3	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no 4.3,Page no12,PWD SR 2015-16)	Cum	4.54	5070.00	Rupees five thousand seventy only
4	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work (pwd sr2015-16,p.no13,sno4.11)	sqm	19.53	6198.00	Rupees six thousand one hundred ninety eight only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri SAMBASHIVA REDDY C	
				Rate	Rate in Words
5	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe55 0(pwd sr2015-16,p.no17,s.no4.46)	Qit.	19.53	6500.00	Rupees six thousand five hundred only
6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecificationS.Specification no.KBS 4.6.2 (pwd sr2015-16, p.no15/4.31)	sqm	126.50	306.00	Rupees three hundred six only
7	Removing B.S slab of drain and stacking (P.No 25 I.No 5.32)	sqm	250.00	63.00	Rupees sixty three only
8	Refixing stone slabs of drains and pointing in CM(1:3)(P.No 25 I.No 5.33)	sqm	250.00	78.62	Rupees seventy eight and paise sixty two only
9	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick(P.No 25 I.No 5.31.1)	sqm	60.00	663.00	Rupees six hundred sixty three only
10	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. (PWD SR 2015-16 P.133/I.17.1)	Cum	237.00	73.35	Rupees seventy three and paise thirty five only
11	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve thedesired density, complete as per clause 401 of MORT & H For Grading-II Materia(PWD SR2015-16, P.NOI51/20.5.2)	sqm	276.00	1449.10	Rupees one thousand four hundred forty nine and paise ten only
12	KSRRB M1400-14.2. Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density. Material Using Scrining Crushable Type such as Moorum or Gravel Grading - III (Manual) Clause : 404 (P.154/I.20.15.3 PWD SR - 2015-16).	Cum	110.40	1351.00	Rupees one thousand three hundred fifty one only

C Samba Shiva Reddy
Signature of the Contractor

Executive Engineer
Yelahanka Division,
BBMP, Bengaluru-64

Printed on : 08-Dec-2015